



LGU - LINGAYEN

**BAC**

BIDS AND AWARDS COMMITTEE

HON. LEOPOLDO N. BATAOIL  
 Municipal Mayor

Chairperson

JOAN JUDE R. LOPEZ, LLB, MDM  
 Municipal Civil Registrar

Vice-Chairperson

ROBERTO DG. SYLIM  
 Municipal Administrator

BAC Members:

JEANNE IRAYDA N. GOMEZ  
 Municipal Budget Officer

ATTY. DOMINIQUE C. EVANGELISTA  
 Municipal Legal Officer

RAUL A. UNGSON  
 Chief Administrative Officer

ENGR. JEROME V. CANILLAS  
 Municipal Assessor

ARCH. NELCO PAUL P. COQUA, ENP  
 MPOC

Technical Working Group:

LARRY B. FLORES  
 Municipal General Services Officer

ENGR. JOHN SVESTER A. TAPIA  
 Municipal Engineer

NELSON S. GUMAPOD  
 Municipal Accountant

BAC Secretariat:

ARNULFO S. BERNARDO  
 Market Supervisor IV -- HEAD

SHARON S. SISOW  
 Administrative Officer IV

ARISANNE GRACE M. DE GUZMAN  
 Administrative Officer III

CEZAR IAN B. FERNANDEZ  
 Security Officer II

MYRA B. GARCIA  
 Revenue Collection Clerk II

**BID SUPPLEMENT**

In reference to Invitation to Bid for the *Delivery of Installation of CCTV at Lingayen Civic Center (Phase I), Lingayen, Pangasinan* with an Approved Budget for the Contract of *Three Hundred Ten Thousand Pesos (P310, 000.00) only* which was published, where certain components and technical specifications has been overlooked when being encoded. Thus, said procurement shall have the following revisions:

<b>FROM</b>	<b>TO</b>
<b>SECTION VII. TECHNICAL SPECIFICATIONS</b>	<b>SECTION VII. TECHNICAL SPECIFICATIONS</b>
<p><b>Installation of CCTV at Lingayen Civic Center (Phase I), Lingayen, Pangasinan</b></p> <p><b>CCTV SYSTEM</b>  <b>Specifications/Minimum Requirements:</b>            5MP Bullet camera            32 channel digital video recorder, 5MP            30 amp. Centralized power supply, 12v            BNC connectors            DC plug            6TB storage HDD, 7200RPM</p> <p><b>Inclusions:</b>            RG6 siamese cable with power, 300 meters            Smart Television, 50"            Square box for outdoor cameras            Metal box, XL            Cladding ring            Fiber cable, 1 km            Fiber media converter, 8-channel            Fiber media converter, 4-channel            SC connector            Patch cord            F clamp            THHN cable, #12            Square box, XL            Flat cord, #16            Consumable Hardware            Labor and Installation Cost</p>	<p><b>Installation of CCTV at Lingayen Civic Center (Phase I), Lingayen, Pangasinan</b></p> <p><b>CCTV SYSTEM (TURN KEY)</b>  <b>Specifications/Minimum Requirements:</b>            8 pc IP Camera 5MP Fullcolor                (2 Dome Camera and 6 Bullet Camera)            1 pc 32 Channel NVR – (IT Camera)            30 amp. Centralized power supply, 12v            6TB storage HDD, 7200RPM</p> <p><b>Inclusions:</b>            3 rolls CAT6 outdoor            2 pc Smart Television, 50"            Square box for outdoor cameras            Metal box, XL            Cladding ring            Fiber cable, 1 km – (per roll, single core)            SC connector            Patch cord            F clamp            THHN cable, #12            Square box, XL            Flat cord, #16            Consumable Hardware            Labor and Installation Cost            1 pc POE Switch            1 pc Sport Switch            1 year warranty on services and parts</p>

Issued this 04<sup>th</sup> day of November 2021 at Lingayen, Pangasinan.

Prepared by:

**ARNULFO S. BERNARDO**  
 Head, BAC Secretariat

Certified by:

**JOAN JUDE R. LOPEZ, LLB, MDM**  
 BAC Chairperson