Republic of the Philippines
Province of Pangasinan
MUNICIPALITY OF LINGAYEN

LGU - LINGAYEN

BAC

BIDS AND AWARDS COMMITTEE

BID SUPPLEMENT

Head of Procuring Entity

HON. JOSEFINA "JOAY" V. CASTAÑEDA
Municipal Mayor

Chairperson

ATTY. NEPTHALIE D. PASILIAO
Municipal Legal Officer

Vice-Chairperson

JEANNE IRAYDA N. GOMEZ
Municipal Budget Officer

BAC Members:

LYDIA C. PIOQUINTO
Municipal Administrator

JUDY DL. VARGAS-QUIOCHO
Chief Administrative Officer

ENGR. JEROME V. CANULLAS
Municipal Assessor

ARCH. NELCO PAUL P. COQUIA, EnP
MPDC

JOAN JUDE R. LOPEZ
Municipal Civil Registrar

Technical Working Group:

LARRY B. FLORES
Municipal General Services Officer - HEAD

ENGR. ROMEL L MELENDEZ
Municipal Engineer

NELSON S. GUMAPOS
Municipal Accountant

BAC Secretariat:

SHARON S. SISON
Admin. Officer IV - HEAD

ARCANNE GRACE M. DE GUZMAN
Assistant SB Secretary

MARIANNE E. TAÑEDO
Administrative Officer III

MYRA B. GARCIA
Revenue Collection Clerk II

PRINCESS ROSE O. PINTO
Administrative Aide IV

In reference to Invitation to Bid for the ***Procurement of Solar Early Warning System with CCTV undertaken through Early Procurement Activity*** with an Approved Budget for the Contract of ***Three Million Eight Hundred Thousand Pesos (P3,800,000.00) Only*** which was published, where certain components and technical specifications has been overlooked when being encoded. Thus, said procurement shall have the following revisions:

FROM	TO
SECTION III. BID DATE SHEET (BDS) Clause 19.3 *SECTION VI. SCHEDULE OF REQUIREMENTS* *SECTION VII . TECHNICAL SPECIFICATION*	*SECTION III. BID DATE SHEET (BDS) Clause 19.3* *SECTION VI. SCHEDULE OF REQUIREMENTS* *SECTION VII . TECHNICAL SPECIFICATION*
Solar Early Warning System with CCTV *Inclusions/Specifications/Minimum Requirements:* **IP POE HORN SPEAKER - 18 units** SIP POE, Waterproof IPX5, 50W Equipped with 10 multicast address for receiving 27/7 colourful imaging **Wall Mounting Bracket - 40 units** **Hot deep galvanize 9meters - 8 pieces** Thickness: 2.3mm Weight 35kg **Wireless Device - 10 units** Rohs compliant **Monitor - 1 unit** TV inch: 55 **Lithium Ion Phosphate 100mah Battery - 8 units** Voltage: 24volts Capacity: 100mah Max charger cut-off voltage: 28v Max discharge cut-off voltage: 20v **Solar Panel, 160 watts - 8 units** Peak power (wp): 165W Rated voltage (V): 19.69v Rated Current (A): 10.72A **Lightning Arrester - 8 units** NOT STATED NOT STATED	Solar Early Warning System with CCTV *Inclusions/Specifications/Minimum Requirements:* IP POE HORN SPEAKER - 18 units SIP POE, Waterproof IPX5, 50W Equipped with 10 multicast address for **66** **24/7** colourful imaging Wall Mounting Bracket - **36 units** **Hot Dipped Galvanized 3d fence** **2.4 meter * 5ft – 6 units** Wireless Device - 10 units Rohs **Compliance** Monitor - 1 unit TV inch: **75** **Universal Wall Bracket for 75 inch tv monitor** Lithium Ion Phosphate **200ah** Battery – 8 unit **Voltage: 12.8 volts with bms and active balancer** **Capacity : 200ah** Max charger cut-off voltage : **14.2v** Max discharge cut-off voltage : **11.5v** Solar Panel, **615 watts** - 8 units Peak power (wp): **615W** Rated voltage (V): **40.69v** Rated Current (A): **18.72A** Lightning Arrester - 8 units **Ground rod 5/8" x 4¼ feet copper plated with ground clamp** **grounding wire (8.0mm² THHN/THWN)** **Galvanized Steel Electrical Tubular poles – 6 unit** ***Minimum Requirements/Specification:*** **Hot deep galvanize 35ft** **Thickness 2.3mm** **Weight 125kg** **Pole Antenna 70ft 1 set** ***Minimum Requirements/Specification:*** **1¼ s40 GI pipe Fabricate 70 ft** **Metal Enclosure Box – 16 unit** ***Minimum Requirements/Specification:***

CamScanner

Republic of the Philippines
Province of Pangasinan
MUNICIPALITY OF LINGAYEN

	Manufactured : steel Thickened water proof sealing strip Power supply mounting plate Reinforced hinge and waterproof lock Specification With divider 45*55*35 mm Metal cage Box – 8units *Minimum Requirements/Specification:* Fabricate Manufactured : Stainless steel 50*100*40mm Metal Cable Tie – 72 pcs Guy Wire 3.0 – 1 Roll Turn Buckle – 50 pcs Aluminum Rails 2.4 mm – 16 units Breaker AC – 8 pcs Breaker DC- 8 pcs Connector Mc4 – 8 pcs Surge protection AC – 8 pcs Surge protection DC – 8 pcs PVC pipe ½ 20 units Bracket for Solar Panel 6 units Fabricate Photovoltaic cable 8mm DC cable – 1 roll 100m 1kw Solar Inverter – 8 units *Minimum Requirements/Specification:* Rated input coltage : 220/230 Vac Input voltage range (170 ac – 280ac)_+2% Frequency : 50Hz/60Hz Battery Rated Voltage : 12v Battery support : lead acid AGM, Gel, lifepo4 Built in AC charger, max 15A Charger current Built – in MPPT charger 40A max PV input 100v voc, maximum 600w (12v) 1200w (12.8) Transformer type : toroidal AC Output Pure sine wave Protection high & low Voltage alarm Automatic self-protect short circuit and shut down Over temperature alarm overload alarm Dimension : size 396*294*145 GW(kgs): 11kg with Installation ---nothing follows---

Issued this 12th day of January 2026 at Lingayen, Pangasinan.

Prepared by:

SHARON S. SISON
BAC Secretary

Noted by:

ATTY. NEPTHALIE D. PASILIAO
Chairperson, BAC

CamScanner